

Networking

1. Single Mode Fiber installed, terminated, labeled and tested from 1st Floor Mechanical Room to Commencement Closet on 2nd Floor
2. Single Category 6 network drop installed, terminated, labeled and tested (keystone patch panel jacks) from Commencement Closet to each Room label 204, 205 and 206 in existing single gang box
3. Thirteen Category 6 network drops installed, terminated, labeled and tested (keystone patch panel jacks) from Commencement Closet to Room LB203 in designated location on diagram. Single Gang box will need to be installed.
4. Thirteen Category 6 network drops installed, terminated, labeled and tested (keystone patch panel jacks) from Commencement Closet to Room LB202 in designated location on diagram. Single Gang box will need to be installed.
5. Single Category 6 network drop installed, terminated, labeled and tested (keystone patch panel jacks) from Commencement Closet to Room LB201 in designated location on diagram
6. Seven Category 6 network drops installed, terminated, labeled and tested (keystone patch panel jacks) from Commencement Closet to Room LB200 in designated location on diagram.

Electric

1. Six additional outlets on single 20-amp circuit placed next to each of the six data single gang boxes in Room LB203
2. Six additional outlets on a single 20-amp circuit placed next to each of the six data single gang boxes in Room LB202
3. Additional outlets/circuit in LB200 for installation of four cubicles. Confirm with MAC General Services before installation